

REV	DESCRIPTION	BY	DATE
Δ	CHANGE TY-B TO TY-D AND CODE 3076 6001 TO 3076 6035	AMP	04/19/2024

A. SUMMARY OF QUANTITIES			1	2	3	4	5	6	7	8	9	10	11	12
			500	500	502	502	731	305	3076	3076	251	251	251	700
			6001	6001	6001	6001	6011	6002	6035	6066	6034	6073	6273	6001
			NORTH LEVEE MOBILIZATION	SOUTH LEVEE MOBILIZATION	NORTH LEVEE BARRICADES, SIGNS, AND TRAFFIC HANDLING	SOUTH LEVEE BARRICADES, SIGNS, AND TRAFFIC HANDLING	HERBICIDE TREATMENT	SALV, HAUL & STKPL RCL ASPH PV (0 TO 2")	D-GR 1 1/2" HMA TY-D PG 64-22	TACK COAT	REWORK BS MATL (TYC)(8") (ORD COMP)	REWORK BS MATL (TYC)(10") (ORD COMP)	REWORK BS MATL (TYC)(12") (ORD COMP)	POTHOLE REPAIR
			LS	LS	LS	LS	AC	SY	TON	GAL	SY	SY	SY	SY
SHT 14	8+25.00	30+50.00					1.35	5,931	489	712	494			
SHT 15	30+50.00	54+50.00					1.46	6,507	537	781	533			
SHT 16	54+50.00	68+86.00					0.86	3,830	316	460	319			
SHT 16	68+86.00	77+50.00					0.54	2,410	199	289			192	
SHT 17	77+50.00	97+00.00					1.16	5,200	429	624			433	
SHT 18	97+00.00	120+00.00					1.37	6,131	506	736			511	
SHT 19	120+00.00	134+21.00					0.85	3,789	313	455			316	
SHT 19	134+21.00	144+00.00					0.59	2,617	216	314	218			
SHT 20	144+00.00	168+00.00					1.43	6,398	528	768	533			
SHT 21	168+00.00	192+00.00					1.43	7,226	596	867	533			100
SHT 22	192+00.00	199+34.93					0.48	1,954	161	235	163			
<b>SUBTOTAL TOTALS - NORTH LEVEE</b>			<b>1</b>		<b>1</b>		<b>11.52</b>	<b>51,993</b>	<b>4,290</b>	<b>6,239</b>	<b>2,794</b>		<b>1,452</b>	<b>100</b>
SHT 23	-0+51.89	19+00.00					0.96	4,235	349	508			434	
SHT 24	19+00.00	27+14.64					0.41	1,812	149	217			181	
SHT 24	27+45.19	43+00.00												
SHT 25	43+00.00	55+17.53												
SHT 25	57+25.85	60+03.50												
SHT 25	60+03.50	67+00.00					0.37	1,615	128	185			155	
SHT 26	67+00.00	90+50.00					1.19	5,253	433	630		522		100
SHT 27	90+50.00	94+88.51					0.19	843	70	101		97		
SHT 27	95+02.75	109+37.40					0.69	3,050	250	363		319		
SHT 28	113+85.71	126+86.17					0.66	2,913	238	347		289		
SHT 28	130+38.84	133+50.00					0.16	692	57	83		69		
SHT 29	133+50.00	139+36.83					0.35	1,531	108	156		130		
SHT 29	140+76.70	146+00.17					0.27	1,172	97	141		116		
SHT 29	149+03.16	155+00.00					0.26	1,162	123	179		133		
SHT 30	155+00.00	159+17.36					0.25	1,113	92	134		93		
SHT 30	160+46.40	178+00.00					1.05	4,676	386	561		390		
SHT 31	178+00.00	201+00.00					1.58	6,133	506	736			511	
SHT 32	201+00.00	207+28.32					0.45	1,738	143	209			140	
SHT 32	210+48.78	220+32.59					0.69	2,897	239	348			219	
<b>SUBTOTAL TOTALS - SOUTH LEVEE</b>				<b>1</b>		<b>1</b>	<b>9.53</b>	<b>40,835</b>	<b>3,368</b>	<b>4,898</b>		<b>2,158</b>	<b>1,639</b>	<b>100</b>
<b>TOTALS FOR N/S LEVEES</b>			<b>1</b>	<b>1</b>	<b>1</b>	<b>1</b>	<b>21.05</b>	<b>92,828</b>	<b>7,657</b>	<b>11,137</b>	<b>2,794</b>	<b>2,158</b>	<b>3,091</b>	<b>200</b>

CivilTech Engineering, Inc.  
 C:\2022\10018574\_Galv Levee Road Project\Drawings\Sheets\SUMMARY OF QUANTITIES.dwg Apr. 19, 2024

**CivilTech**  
A WOOLPERT COMPANY

11750 KATY FREEWAY, SUITE 1260  
HOUSTON, TEXAS TX, 770079  
(346) 409-2067  
Fax (281) 304-0210  
Registration No. F-382

**GALVESTON COUNTY**  
ENGINEERING DEPARTMENT

SUMMARY OF  
QUANTITIES

DESIGN: P.G., D.E.S.	FOR GALVESTON COUNTY ENGINEERING DEPARTMENT USE ONLY
DRAWN: P.G., D.E.S.	
DRAWING SCALE	
AS SHOWN	
GALVESTON COUNTY PM	
PM, MICHAEL SHANNON	
SHEET NO. 03 OF 37	