

THE COUNTY OF GALVESTON

RUFUS G. CROWDER, CPPO CPPB
PURCHASING AGENT

COUNTY COURTHOUSE
722 Moody (21st Street)
Fifth (5th) Floor, Purchasing
GALVESTON, TEXAS 77550
(409) 770-5371

ERIN S. QUIROGA, MBA, CPPB
ASST. PURCHASING AGENT

November 15, 2024

PROJECT NAME: Bacliff Drainage Improvements

SOLICITATION NO: ITB 24-025

RE: Addendum #1

To All Prospective Bidders:

The following information is being provided to aid in preparation of your bid submittal(s):

Question #1: *Please verify the cable size of the Articulated Concrete Block (ACB). The 3/4 inch cable diameter per the ACB specs is not the industry standard.*

Response: The standard cable size per the manufacturer specifications is 20 mm. The manufacturer confirmed that 1 inch hole diameter is large enough for all cabling of ACB with 20 mm Polyester cables. The latest cable specifications have been included in the revised project manual and attached to the addendum.

Question #2: *Would you please post the pre-bid meeting attendees list?*

Response: Attached you will find the pre-bid meeting attendees list.

Question #3: *Could we submit a proposal for the CMT scope needed on this project?*


Response: CMT has already been selected on this project and we are not accepting bids for CMT.

If you have any further questions regarding this solicitation, please address them to the following representative or contact the Purchasing Department at (409) 770-5371.

Rufus G. Crowder, CPPO CPPB
Galveston County Purchasing Agent
722 Moody, Fifth (5th) Floor
Galveston, Texas 77550
E-mail: rufus.crowder@co.galveston.tx.us

Please excuse us for any inconvenience that this may have caused.

Sincerely,



Rufus G. Crowder, CPPO CPPB
Purchasing Agent
Galveston County

PRE-BID CONFERENCE
 BACKLIFT DRAINAGE IMPROVEMENTS
 GALVESTON COUNTY, TEXAS

The Pre-Bid Conference for ITB 24-025 will be held on Tuesday, November 5, 2024 at 10:00 AM at 722 Moody, (21st St.), 5th Floor, Purchasing Department, Galveston, TX 77550

PRINTED NAME	SIGNATURE	COMPANY NAME	E-MAIL ADDRESS	PHONE
Bretus Crowder	<i>Bretus Crowder</i>	Galv. City Purchasing	bretus.crowder@co.galveston.tx.us	409 770-5372
Michael Shannon	<i>Michael Shannon</i>	Galv. City Engineering	michael.shannon@co.galveston.tx.us	409 770-5453
Nancy Baker	<i>Nancy Baker</i>	Galv. City Engineering	nancy.baker@co.galveston.tx.us	409 770-5556
Tammy Dickey	<i>Tammy Dickey</i>	Galv. City Purchasing	tammy.dickey@co.galveston.tx.us	409 770-5373
Don Stephanik	<i>Don Stephanik</i>	Cornett Fleming	dstephanik@gfnet.com	
Miguel Tellez	<i>Miguel Tellez</i>	Cornett Fleming	mtellez@gfnet.com	
Brandon Flores	<i>Brandon Flores</i>	T Construction	bflores@tconstructionllc.com	
Mounika Jella	<i>Mounika Jella</i>	Cornett Fleming	mjella@gfnet.com	
Chad LeBlanc	<i>Chad LeBlanc</i>	Teamwork Construction	chad@teamworkconstruction.net	
Ella Crutcher	<i>Ella Crutcher</i>	Tandem Services	tandem@tandemservices.com	
Shilpa Krabinski	<i>Shilpa Krabinski</i>	Gedeon Engineering	shrabinski@gedeongr.com	
David Rankin	<i>David Rankin</i>	Cornett Fleming	drankin@gfnet.com	
Rafael Castro	<i>Rafael Castro</i>			

Carvin T

Special Specification
Articulated Concrete Block

SPECIFICATIONS
FOR

CHANNEL LOCK II™
FLEXIBLE REVETMENT SYSTEM

CLASS 450
WITH
POLYESTER REVETMENT CABLES

**TABLE OF CONTENTS FOR
EROSION CONTROL**

PARAGRAPH	PARAGRAPH TITLE	PAGE
PART 1 - GENERAL		
1.1	SCOPE OF WORK	01
1.2	REFERENCES	01
1.3	DELIVERY, STORAGE AND HANDLING	01
1.4	MEASUREMENT	01
1.5	PAYMENT	01
PART 2 - PRODUCTS		
2.1	DESIGN CRITERIA	02
2.2	CELLULAR CONCRETE BLOCKS	02
2.3	CELLULAR CONCRETE BLOCKS W/ CABLES	02
2.4	CABLE REQUIREMENTS	02
2.5	FILTER FABRIC	03
PART 3 - EXECUTION		
3.1	FOUNDATION PREPARATION	03
3.2	INSTALLATION OF CELLULAR CONCRETE MATS	03
3.3	FINSHING	04
3.4	CONTRACTOR QUALITY CONTROL	04

PART 1 - GENERAL

1.1 SCOPE OF WORK:

This item consists of furnishing and installing an interlocking flexible revetment system (cellular concrete blocks) in accordance with the lines, grades, design and dimensions shown on the plan and drawings and specified herein.

1.2 REFERENCES:

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designations only.

5.1.1. American Society for Testing and Materials (ASTM) Publications.

ASTM C 33-97 Concrete Aggregates

ASTM C 140-91 Sampling and Testing Concrete Masonry Units

ASTM D-7277 Standard Test Method for Performance Testing of Articulating Concrete Block (ACB) Revetment Systems for Hydraulic Stability in Open Channel Flow

ASTM D-7276 Standard Guide for Analysis and Interpretation of Test Data for Articulating Concrete Block (ACB) Revetment Systems in Open Channel Flow.

ASTM D 4268-93 Testing Fiber ropes

5.1.2. US Federal Highway Administration (FHWA) and US Bureau of Reclamation (USBR)

FHWA RD-89-199 Hydraulic Stability of Articulated Concrete Block
Revetment Systems During Overtopping Flow.

1.3 DELIVERY, STORAGE AND HANDLING OF MATERIALS:

Materials delivered to the site shall be inspected for damage, unloaded and stored with the minimum of handling. Contractor may designate a storage site at the project for materials to be delivered and stored prior to placement if needed. Storage site to be approved by the Contracting Officer, if necessary. Materials shall not be stored directly on the ground and shall be kept free of dirt and debris. Materials shall be so handled as to ensure

delivery to the site in sound undamaged condition. Synthetic geotextiles that are not to be installed immediately shall be protected from the direct sunlight.

1.4 MEASUREMENT:

Unit of measurement for the cellular concrete blocks shall be by the square foot of surface area satisfactorily covered with the cellular concrete blocks.

1.5 PAYMENT:

Unit of payment for acceptable cellular concrete blocks placed will be made at the contract unit price per square foot for "cellular concrete blocks", which price shall include costs of furnishing, hauling and placing the cellular concrete blocks with cables.

PART 2 - PRODUCTS

2.1 DESIGN CRITERIA:

The interlocking flexible revetment system shall be as described herein known as Channel Lock II or an approved equal. Hydraulic test data and block performance according to FHWA-RD-89-199 will be required to be submitted for approval by the Contracting Officer. The concrete blocks shall be a minimum of 4.5' Thick, have a Net Weight/Area of 36 lbs. PSF, be open cell blocks, and shall withstand water flow velocities of 26.1 FPS and critical shear stress (at horizontal) of 31.8 lbs. PSF on a 1V:2H slope in direction of flow.

2.2 CELLULAR CONCRETE BLOCKS:

The cellular concrete blocks shall be octagonal shaped with interlocking components four directional within a 15" module. Each component shall resist horizontal movement when interlocked into adjacent blocks. (Interlock is hereby defined as the inability to pull apart or separate when one component is placed in conjunction with another component). The assembled blocks shall be the open-cell type and have a void space of approximately 20% to allow for re-vegetation. Maximum water absorption shall be 7%.

2.21 Concrete Materials:

The compressive strength of the concrete shall be a minimum of 4000 PSI at 28 days. The core compressive strength shall not be less than the minimum and test cores shall be tested at the engineer's option. Test procedures shall be in accordance with ASTM C 140-91. Cores failing to meet the minimum compressive strength requirements shall be cause for rejection of the represented lot by the engineer.

2.22 Aggregate:

The aggregate shall meet the requirements of ASTM C 33-97, except for grading. Aggregate grading shall be reasonably consistent and shall be well-graded from the maximum size which can be conveniently handled with available equipment

2.3 CELLULAR CONCRETE BLOCKS WITH CABLES:

The cellular concrete blocks shall have cables and shall be installed as an assembly of concrete blocks connected by the use of revetment cables. The cables will extend through 2 or more tunnels within the blocks to bind the mattresses in both the longitudinal and lateral directions. Cable shall conform to ASTM D 4268-93.

2.4 CABLE REQUIREMENTS:

Cable shall be constructed of high tenacity, low elongation and continuous filament polyester fibers. Cables shall consist of a core construction comprised of parallel fibers contained within an outer jacket or cover. The weight of the parallel core shall be between 65 to 70 percent of the total weight of the cable. The revetment cable shall have the following minimum physical properties:

Nominal Cable Diameter:	20 mm
Approximate Strength Lbs.	3,700
Weight	Yield – 41.3 ft/lb.

2.41 The revetment cable shall exhibit good to excellent resistance to most concentrated acids, alkalis and solvents. Cable shall be impervious to rot, mildew and degradation associated with marine organisms. The materials used in the construction shall not be affected by continuous immersion in fresh or salt water.

2.42 Selection of cable and fittings shall ensure a safe design factor for mattresses being lifted from both ends, thereby forming a catenary. Consideration shall be taken for the bending of the cables around hooks or pins during lifting. Revetment cable splicing fittings shall be selected so that the result splice shall provide a minimum of 75 percent of the minimum rated cable strength. Fittings such as sleeves, stops and washers shall be in accordance with manufacturer’s recommendations unless otherwise shown.

2.43 Elongation Requirements:

Requirements listed below are based upon stabilized new and dry cable. The tolerance of these values is plus or minus 5 percent.

	% Breaking Strength		
	<u>10%</u>	<u>20%</u>	<u>30%</u>
Permanent Elongation	0.7	1.8	2.6
(While Working)			
Elastic Elongation	0.6	1.4	2.2
Total Stretch	1.3	3.2	4.8

2.5 FILTER FABRIC:

The filter fabric used for cellular concrete blocks shall be in accordance with the Engineer's specifications.

PART 3 - EXECUTION

3.1 FOUNDATION PREPARATION:

Areas on which filter fabric and cellular concrete blocks are to be placed shall be constructed to the lines and grades shown. The subgrade for the cellular concrete blocks shall be free of voids, pits and depressions. Voids, pits and depressions shall be brought to grade by backfilling in accordance with the Engineer's applicable specifications. Obstructions, such as roots and projecting stones larger than 1 inch remaining on the surface, shall be removed and the soft or low-density pockets of material removed shall be filled with selected material and compacted to a minimum of 90% proctor density.

3.12 Perimeter:

Excavation and preparation for anchor trenches, side trenches, toe trenches and aprons shall be done in accordance to the lines, grades and dimensions shown on the plans.

3.13 Inspection:

Immediately prior to placing the filter fabric and cellular concrete blocks, the prepared area shall be inspected by the Contractor and approved before the fabric or blocks are placed thereon.

3.2 INSTALLATION OF CELLULAR CONCRETE MATTRESSES:

3.21 Filter Fabric:

Placement of filter fabric shall be installed in accordance with the SECTION 3.3.1 and 3.3.2.

3.22 Placement of Cellular Concrete Mats:

Cellular concrete mats shall be placed within the limits shown. The blocks shall be interlocked in a manner which discourages any vertical displacement or horizontal movement. The cellular concrete mats shall be placed on the

filter fabric in such a manner as to produce a level surface. Individual blocks which are hand installed and hand threaded cables shall be installed according to manufacturer's recommendations. No more than 200 linear feet of filter fabric shall be laid before covered with concrete blocks. Fabric installed more than two (2) days not covered by blocks shall be lifted and the surface of the slope inspected for slope defects. The Contracting Officer will require uncovered fabric to be lifted after heavy rainfall to inspect for slope damage. The manufacturer, Contractor and Client shall discuss subgrade preparation, geotextile and cellular block placement at the pre-construction meeting to ensure that all parties are aware of the issues regarding installation. The manufacturer of the cellular concrete mats shall be present during the first week of block placement to assist the Contractor. The Contractor shall furnish a certificate from the manufacturer or an authorized representative thereof stating that the blocks were installed correctly. Final acceptance and approval of the installation will be made by the Contracting officer.

3.23 Quality Control:

Equipment shall be minimized on the installed concrete blocks until backfill or topsoil is placed over the revetment system to refrain from breaking or damaging any blocks. Any blocks broken or damaged shall be repaired prior to final inspections.

3.24 Grouting:

Any areas where there are partial blocks (to avoid small blocks with reduced hydraulic stability) shall be grouted. Joints where block interlock is discontinuous shall be grouted. Field placed grout shall have a compressive strength of 4,000 psi, the durability properties of the ACBM concrete, and shall meet the ACBM manufacturer's requirements. All cable ties and anchoring shall be completed prior to placing the grout.

3.3 FINISHING:

3.41 The voids of the cellular concrete blocks for the limits shown shall be filled with gravel or topsoil per the specifications. At no time shall more than 500 lineal feet of blocks be exposed not backfilled. Prior to backfill, the blocks surface shall be inspected for damage. Individual blocks which are cracked and reduce the individual block weight to 1/3 shall be replaced prior to the placement of backfill.

3.4 CONTRACTOR QUALITY CONTROL:

The Contractor shall inspect for compliance with contract requirements and record the inspection of operations including but not limited to the following as applicable:

- (1) Preparation of surface to receive cellular concrete blocks or mattresses
- (2) Individual concrete blocks and filter fabric soundness and free of defects
- (3) Cables and fittings - breaking strength
- (4) Assembly of cellular concrete blocks bound by cables to form cellular concrete mattresses
- (5) Placement of blocks or mattresses and filter fabric on the prepared subgrade